



***Monitoring & Data Management  
in the Project  
"Cityringen Copenhagen"***


**ANGERMEIER INGENIEURE GmbH**

**Dieter Heinz**



- Metro Copenhagen,
  - History of the Metro
  - Cityringen – what does it mean?
  - Scope of project
  - Specials in realization
  
- Scope of our project activities
  - Geodetic and geotechnical measurement tasks
  - Data management
  - Visualization and data management in a project-specific GIS-Database

- Existing Metro lines M1 und M2
- Operating since 2002
- 22 stations thereof 9 underground
- Length 21 km
- 1 maintenance center







Metro Lines



Branch to



Connection to



- One of the most modern Metro systems
- Driverless transportation
- Frequency 100 seconds
- 24h per day in operation
- Transportation of total 130.000.000 people/year (=365 000/day)
- New: Connection to central railway main station and 2x „S-Tog“ train stations (Nørrebro / Østerport)
- The both Metro's there are a fast, safe and environmentally friendly transportation established





# CMT COPENHAGEN METRO TEAM

- Italian joint venture


- Salini / Impregilo (leader)
- Tecnimont
- Seli



- Launching of research 2009/2010
- CMT starts construction in Nørrebroparken in 2011
- Start of the first measurements in October 2011
- Structural works until Spring 2017
- Professional Operation starts in Summer 2019
- Construction costs about ca. 21.3 Mrd DKK (= 2.8 Mrd EUR)




- Start of TBM works in 2013, end in 2017
- Operating simultaneously up to 4 TBM's
- Type EPB-shields (Earth Pressure Balance)





Overview construction progress TBM's




Main structure works at stations in final stage (inner linings, concourse level, technical rooms)

69% of TBM Tunnel finished



- Construction in surrounding properties hides always great risks, especially in such dimensions
- Very old buildings, many „listed buildings“
- Foundation of old buildings on oak piles,
- High groundwater level







- Station is located very close to a church
- Foundation of the church and the adjacent old buildings on countless oak posts
- Height 45m
- Diameter of Dome 31m
- Construction time 1740 – 1894  
 for many decades a ruin






- Tunnel tubes over each other



Metro station



- Half of station below a small channel





- Joint Venture

- GEODATA Ziviltechnikergesellschaft mbH (Austria)



- ANGERMEIER INGENIEURE GmbH (Germany)



➔ SMT Denmark ApS





- tasks and responsibilities:
  - geodetic monitoring
    - High precision levelling measurements
    - Automatic 3D-Monitoring (installation, maintenance)
    - Manual 3D measurements
  - geotechnical monitoring
    - Manual inclinometer measurements
    - Automatic inclinometer (installation, maintenance)
    - Strain Gauges (installation, maintenance)
    - Automatic extensometer (installation, maintenance)
    - Manual extensometer measurements
    - Liquid levelling systems (installation, maintenance)
  - Maintenance of database (KRONOS)



- High precision Levelling






- 4.000 leveling bolts
- 835.000 measurements
- 5-8 crews in parallel





- Automated 3D-Monitoring Systems

- 100x Leica TM30 0,5"
- 79.600.000 measurements





- 3D Net of 4 connected ATS and 3 additional independent working ATS in backyards at SKP





- 3D Net of 4 connected ATS and 3 additional independent working ATS in backyards at SKP

Result:  
3D –  
Displacement  
Scale 1:1





- **Inclinometer**
  - 158 inplace inclinometer chains
  - 3 probes for manual readings
  
- **Extensometer measurements**
  - 30 boreholes equipped with up to 5-fold sensors
  
- **Groundwater measurements**
  - 225 boreholes with open standpipe water level transmitter



- strain gauges  
 1850 sensors installed to monitor temporary struts in stations
- readings every 4 hours
- liquid leveling systems  
 28 sensors installed to monitor Marmorkirke







Photo: Geodata Messtechnik GmbH  
 Photo: SMT Denmark ApS  
 Drawing: Copenhagen Metro Team I/S

- Requirements of the Client (abstract)
  - Results of all monitoring measurements
  - Thresholds with automatic alarming
  - Geotechnical and hydrogeological data
  - Groundwater control systems
  - Tunnel alignment, station data
  - Construction progress (piling, d-walls)
  - TBM-parameter
  - Building information
  - ...





- KRONOS Database




- Access to Database by various disciplines of the project
  - Automatic input data from sensors / TBM
  - Input (monitoring, groundwater, environmental departments)
  - Read / evaluate / checking (client, consultant, designer)





- For the monitoring data from critical areas and for the TBM data the KRONOS alarming functions and services are used.
- They allow for the configuration of a comprehensive alarm plan comprising alarm rules, alarm levels and alarm notification targets.

Monitoring network layout





- Alarm workflow shown as an example of a 3D point



Measurement exceeds limit value → Alarm → message to relevant user → red or yellow triangle in planview. For deactivation: alarm has to be confirmed in Kronos alarm report

Show Alarms for Monitor Points and Importources  
 Show Alarms for Monitor Points  
 Show Alarms for Importources  
 Show Current Alarms  
 Show Alarm History  
 Show confirmed alarms also

**Date Filter**  
 Alarms started after:   
 Alarms started before:   
**Importource Filter**  
  
Wildcards (\*) can be used. Multiple items separated by semicolons.

**Monitor Point Filter**  
 3D Target:   
 04\_MGN | ØS0011 |   
 Alternative Monitor Point Name:   
 Alarm Levels:  All  
 Alarm  Alert  PreAlert


Level	Construction	Monitor Object	Monitor Point	Alt. Monitor Point	Importource	Alarm started	Alarm notification	Alarm ended	Description	Confirmed	Date confirmed	Confirmation Text	User Confirmed
Alarm	04_MGN	ØS0011	ØS0011-RP103	42179		22.12.2015 21:57	23.12.2015 06:57		Heave exceeds limit of 10.0 mm...	<input checked="" type="checkbox"/>	23.12.2015 07:24	under review	



- Select a Station / Tunnel stretch  
define add. Information




- Overview  
in planview






- Detail visualization of results
  - Single diagram 3D (time/displacem. -vertical/-longitudinal/-lateral)



- Detail visualization of results
  - Single diagram 3D (time/displacem. - vertical/-longitudinal/-lateral)


Piling works / 1. grouting / excavation of shaft / 2. grouting / 3. grouting

Warning (y) /  
 Alarm Limit (r)






- Detail visualization of results
  - Combination of diagrams (leveling bolt & water level)




Water level sensor  
Leveling bolt



- Detail visualization of results
  - Combination of diagrams (3D & leveling bolt & liquid level)


Frederikskirke or  
 Marmorkirke MMK:  
 Liquid level sensor /  
 Leveling bolt /  
 3D prism






- Detail visualization of results
  - Combination of diagrams (3D & liquid level & leveling bolt)


3D prism



Liquid level




leveling bolt




- Reports / documents

- Reports: definition of graphs for external documentation
- Documents: calibration protocols, soil investigations, ...



The screenshot shows the 'Reports' application window. On the left is a tree view containing various report categories such as 3D, Alarming, Crack Meter, Edensometer, GSM Reports, Levelling, and Settlement Lines. The 'Depth Displacement' report is selected. The main area displays the configuration for this report, including parameters like 'Parameter Set', 'Monitor Points', 'Date range', 'Measurement dates', 'Borehole', and 'Axis Scale'. A 'Create Report' button is visible at the bottom of the configuration area.



The screenshot shows the 'Documents' application window. On the left is a tree view of document folders, including 1D Network Adjustment, 3D Network Adjustment, Additional Soil Investigation, and many others. The 'TM3D' folder is selected. The main area displays a document preview for 'Manufacturer Confirmation'. The document text includes: 'Garantie du fabricant', 'Certificación del fabricante', 'Conferma del fabbricante', and 'Herstellerbestätigung'. It also contains technical details and a signature.



- During the last excavation level inside a shaft a huge leakage between the piles was detected
- Together with groundwater a huge amount of sand was washed in the station pit
- One building close to the leakage area was evacuated during the night





- Together with mitigation measurements and permanent monitoring with additional leveling measurements and a high frequency running 3D system,
- settlements of the adjacent buildings of only 3-5 mm occur, so the residents of that building could go back after 2 days.
- The building was lifted up after leakage closing with grouting beyond the building





- With a well-organized team and strictly procedures
  - the daily measurements will be performed in the required precision
  - all systems will be installed quickly
  - all systems has to be permanently maintained
- The key element KRONOS guarantees:
  - All measurements will be stored in the right structure, also with increasing measurement effort
  - All project participants are able to display results and export important information
  - Early warning and alert when thresholds are exceeded

➔ For the success of the whole project



Thank you very much for your attention!

And thanks to the  
Client

**Metroselskabet**

And the Contractor

**CMT** COPENHAGEN METRO TEAM